



NOTES

- I. GROUND SHALL BE PRE-WETTED PER SOILS ENGINEER DIRECTIONS PRIOR TO PLACEMENT OF CONCRETE.
- 2. GRATE SHALL BE BOLTED TO 1/2" X 4 1/2" GALV. ANCHOR BOLTS SET IN CONCRETE.
- 3. MATERIAL FOR CONSTRUCTION OF DOWNDRAIN SHALL BE CONCRETE REINFORCED WITH 6" X 6" WI. 4 X WI. 4 WELDED WIRE FABRIC.
- 4. DOWNDRAIN TO PIPE TRANSITION SHALL BE SET 2' MIN. FROM ROAD RIGHT-OF-WAY.
- 5. GRATE SHALL BE HOT DIP GALVANIZED AFTER FABRICATION.

Revised	Drawn J.A. POT	TS Date 9/21/90	CITY	OF	COR	
9/90	Approved	Date /2-/2-90	PUBLIC	WORKS	DEPARTM	
	Joseph R. Palencia		DOWNDRAIN TO PIPE TRANSITION			220-
	Director of		THIPE I	KANSH	ION	2.5