



NOTES

1. INLET CAN BE PRECAST MANUFACTURED CONCRETE UNIT OR CAST IN PLACE DESIGNED FOR H-20 LOADING.
2. REINFORCING SHALL BE #4 BARS @ 12" O.C. (MAX.) EACH WAY OR 4"X4"-6-6 GAUGE W.W.F. IN THE WALL AND BASE.
3. ADD 2" CONCRETE COLLAR FOR DETACHED SIDEWALK.
4. PLACE CAST IRON HOOD, FRAME AND GRATE. D&L FOUNDRY MODEL I-3541, 3542, 3543 OR EQUAL.

YUBA COUNTY DEPARTMENT OF PUBLIC WORKS	
DRAIN INLET	
APPROVED BY:	8-29-06 DATE:
402	