NOTES FOR TYPE 1 TREE WELL

- 1. THE COVER SHALL BE MADE OF PERMEABLE CONCRETE WITH A MINIMUM COMPRESSIVE STRENGTH OF 1200 PSI (8.5 MPa) AND SHALL BE CAST—IN PLACE OR PRECAST "AGRIPERM" OR EQUIVALENT. CAST—IN—PLACE CONCRETE SHALL CONSIST OF ONE PART CEMENT TO FOUR PARTS 3/8" (10 mm) GRAVEL AND APPROXIMATE 4 GALLONS (15 LITERS) OF WATER PER 94 LB (42.5 kg) OF CEMENT. THE GRAVEL SHALL BE CLEAN WITH FINES REMOVED. THE CONCRETE MIXTURE SHALL BE DEPOSITED AS NEAR AS POSSIBLE TO ITS FINAL LOCATION. THE EXCESS CONCRETE SHALL BE RODDED OFF IN A SAWING MOTION. A SURPLUS OF CONCRETE SHOULD BE MAINTAINED AGAINST THE FRONT SURFACE OF THE SCREED IN ORDER THAT LOW AREAS WILL BE FILLED AS THE SCREED PASSES OVER. RODDING SHALL BE HELD TO A MINIMUM. AFTER THE SURFACE IS FLAT NO OTHER FINISHING WILL BE REQUIRED. CURING COMPOUND TO WHICH WATERPROOFING MATERIALS HAVE BEEN ADDED WILL NOT BE PERMITTED.
- 2. EXISTING SIDEWALKS SHALL BE CAREFULLY SAWCUT PREPARATORY TO INSTALLATION OF TREE WELL COVERS. SAWCUT OVER—RUNS SHALL BE CLEANED AND FILLED WITH EPOXY APPROVED BY THE ENGINEER AND FINISHED TO SIDEWALK GRADE.
- 3. THE PIPE MAY BE CIP, ACP, VCP, ABS, PVC, GALV STL OR ASPHALT IMPREGNATED FIBER DUCT AND IT MAY BE BELL OR PLAIN END.
- 4. AFTER ALL OTHER WORK PERTINENT TO PLANTING HAS BEEN COMPLETED, EACH TREE SHALL BE WATERED IMMEDIATELY WITH A MINIMUM OF 20 GALLONS (75 LITERS) OF WATER, AND REPEATED 2 TIMES IN THE NEXT 3 DAYS, AFTER THE TREE HAS BEEN WATERED AND THE SOIL IS SUFFICIENTLY DRY, THE SOIL SHALL BE GRADED AND TAMPED. THE 3" (75 mm) LAYER OF AGGREGATE SHALL BE PLACED AND GRADED TO ACCEPT THE TREE WELL COVER FIRMLY, WITHOUT ROCKING, AND FLUSH WITH THE TOP SURFACE OF THE SIDEWALK. THE PREMOLDED JOINT FILLER SHALL BE CAREFULLY PLACED TO INSURE A TIGHT FIT WITH THE TOP OF THE JOINT FILLER FLUSH WITH THE ADJACENT SIDEWALK.
- 5. IF CAST-IN-PLACE, THERE SHALL BE A 3 MIL (0.075 mm) PLASTIC LINER BETWEEN WALK AND AGGREGATE

NOTES FOR TYPE 2 TREE WELL

- 1. EXISTING SIDEWALK SHALL BE CAREFULLY SAWCUT PREPARATORY TO LAYING OF CONCRETE BLOCKS OR BRICK. SAWCUT OVER-RUNS SHALL BE CLEANED AND FILLED WITH EPOXY APPROVED BY THE ENGINEER AND FINISHED TO SIDEWALK GRADE.
- 2. THE PIPE MAY BE CIP, ACP, VCP, ABS, PVC, GALV STL OR ASPHALT IMPREGNATED FIBER DUCT, AND IT MAY BE BELL OR PLAIN END.
- 3. NAILS SHALL BE GALVANIZED STEEL BOX.
- 4. AFTER ALL OTHER WORK PERTINENT TO PLANTING HAS BEEN COMPLETED, EACH TREE SHALL BE WATERED IMMEDIATELY WITH A MINIMUM OF 20 GALLONS (75 LITERS) OF WATER AND REPEATED 2 TIMES IN THE NEXT 3 DAYS. AFTER THE WATER HAS SETTLED AND THE SOIL IS SUFFICIENTLY DRY, THE SOIL SHALL BE GRADED AND TAMPED. A 3" (75 mm) LAYER OF AGGREGATE SHALL BE PLACED AND GRADED TO ACCEPT BRICKS FLUSH WITH THE TOP SURFACE OF THE SIDEWALK. THE PREMOLDED JOINT FILLER AND HEADERS SHALL BE CAREFULLY PLACED TO INSURE A TIGHT FIT WITH THE TOP OF THE JOINT FILLER FLUSH WITH THE ADJACENT SIDEWALK.

STANDARD PLANS FOR PUBLIC WORKS CONSTRUCTION

TREE WELL

STANDARD PLAN

519 - 3

SHEET 3 OF 7